



Douglas Partners
Geotechnics | Environment | Groundwater

Integrated Practical Solutions

Report on
Geotechnical Assessment – Urban Capability

Proposed Subdivision
Deferred Areas
Stage 3 Jumping Creek, Queanbeyan

Prepared for
CIC Australia Ltd

Project 88224
August 2015





Douglas Partners

Geotechnics / Environment / Groundwater

Document History

Document details

Project No.	88224.00	Document No.	1
Document title	Report of Geotechnical Assessment – Urban Capability Proposed Subdivision – Deferred Areas		
Site address	Stage 3 Jumping Creek, Queanbeyan		
Report prepared for	CIC Australia Ltd		
File name	\\Dpcannas01\projects\88224.00 - QUEANBEYAN, Urban Capability Study\8.0 Documents\88224.00.R.001.Rev0.Stage 3 Jumping Creek.doc		


Document status and review

Revision	Prepared by	Reviewed by	Date issued
DR	C Reid	M Jones	28 August 2015

Distribution of copies

Revision	Electronic	Paper	Issued to
DR	1		CIC Australia Ltd

The undersigned, on behalf of Douglas Partners Pty Ltd, confirm that this document and all attached drawings, logs and test results have been checked and reviewed for errors, omissions and inaccuracies.

	Signature	Date
Author	 for C Reid	28 August 2015
Reviewer		28 August 2015



Douglas Partners Pty Ltd
ABN 75 053 980 117
www.douglaspartners.com.au
Unit 2, 73 Sheppard Street
Hume ACT 2620
PO Box 1487
Fyshwick ACT 2609
Phone (02) 6260 2788
Fax (02) 6260 1147

Table of Contents

	Page
1. Introduction.....	1
2. Site Description	1
3. Assessment Methods	2
3.1 Information Review	2
3.2 Site Inspection.....	2
3.3 Test Pit Excavation	2
4. Assessment Results	2
4.1 Geology and Hydrogeology.....	2
4.2 Soil Landscape.....	3
4.3 Site Inspection.....	4
4.4 Test Pit Excavation	4
5. Laboratory Testing	5
6. Proposed Development.....	6
7. Comments	6
7.1 General	6
7.2 Development Considerations	7
7.2.1 Site Classification	7
7.2.2 Stability Assessment	7
7.2.3 Soil Erosion	9
7.2.4 Footings.....	9
7.3 Site Preparation and Earthworks	9
7.3.1 Stripping	9
7.3.2 Excavation Conditions	10
7.3.3 Filling Placement	10
7.3.4 Filling Compaction	11
7.4 Drainage.....	11
7.5 House Site Maintenance	11
7.6 Pavements	11
7.7 Salinity.....	12
7.8 Development Constraints.....	12
7.9 Remedial Measures/Site Controls.....	13

7.9.1	Planning/Layout of Development.....	13
7.9.2	Drainage Measures	13
7.9.3	Erosion Management	14
7.9.4	Timing of Works.....	14
7.9.5	Development Restrictions.....	14
7.9.6	Cut – Fill Minimisation on Hillside	14
7.10	Subsurface Investigations	15
7.11	Summary	15
8.	References	15
9.	Limitations	16
Appendix A:	About this Report	
Appendix B:	Drawing 1	
Appendix C:	Explanatory Notes Result of Field Work (Pits 1 – 14)	
Appendix D:	Results of Laboratory Testing (1 page)	
Appendix E:	AGS Guidelines Extract	
Appendix F:	CSIRO Publication	

Report on Geotechnical Assessment – Urban Capability

Proposed Subdivision – Deferred Areas

Stage 3 Jumping Creek, Queanbeyan

1. Introduction

This report presents the results of a geotechnical assessment for urban capability undertaken for the deferred areas within the proposed subdivision known as Stage 3 Jumping Creek in Queanbeyan. The work was requested by CIC Australia Ltd, project developers.

It is understood that consideration is being given to the re-zoning of existing rural land for future residential subdivision and that the NSW Office of Environment and Heritage (OEH) have raised points of concern with respect to soil erodibility and dispersion. Assessment was therefore carried out to address the OEH concerns and to provide preliminary information on geotechnical aspects of the site to assist in planning of the development and for submission to Queanbeyan City Council with the re-zoning application.

The assessment comprised a review of published information, field mapping by a geotechnical engineer, excavation of a series of test pits followed by laboratory testing, engineering analysis and reporting. Details of the work undertaken are given in the report, together with comments relating to soil erosion and dispersion and preliminary comments relating to site development, design and construction practice.

A lot layout and site survey plans were provided by the client for the purpose of the assessment.

This report must be read in conjunction with the notes “About this Report” which are included in Appendix A.

2. Site Description

The overall site comprises two separate areas, one to the east and one to west. Both are irregular in shape covering 4.5 hectares (west) and 5.5 hectares (east). The western area measures about 215 m and 295 m in maximum east-west and north-south dimensions, whilst the eastern area measures about 340 m and 255 m in maximum east-west and north-south dimensions. The site is located at the southern end of the proposed Jumping Creek residential development.

The western site is bounded by the Queanbeyan River to the north and west and undeveloped land to the south and east. The eastern site is bounded by Jumping Creek to the north and undeveloped land on all other sides.

Both sites are undeveloped and partially cleared of trees. They are moderately to heavily grassed with a variable tree and weed density. Extensive rock outcropping and/or cobbles/boulders sub cropping were noted across most of the sites. Uncontrolled filling was limited to existing access tracks and

previous site disturbance (including motor bike mounds). Several areas were noted to contain scrap metal and dumped car bodies.

Site levels in both areas fall in variable directions away from a number of ridgelines and hill tops at grades ranging from 1 in 2 to 1 in 25 (vertical:horizontal) but overall fall is generally to the north west. An overall difference in level from the highest part of the urban development site to the lowest has been estimated to be about 35 – 40 m.

3. Assessment Methods

3.1 Information Review

A review of existing geological, soil landscape and hydrogeological maps was undertaken as part of the assessment. The relevant maps reviewed were as follows:

- 1:100 000 Geological Series Sheet for Canberra (Ref 1),
- 1:100 000 Hydrogeology of the Australian Capital Territory (Ref 2),
- 1:100 000 Soil Landscape Sheet for Canberra (Ref 3).

3.2 Site Inspection

A site inspection was undertaken by a geotechnical engineer on 17 August 2015, which included qualitative assessment of site stability considerations and mapping of site features.

3.3 Test Pit Excavation

The field investigation comprised the excavation of 14 test pits in areas of likely construction (Pits 1 – 14) to depths ranging from 0.3 – 4.0 m using a Kubota KX057.4 mini excavator fitted with a 450 mm wide bucket working under direction of a geotechnical engineer. Disturbed and bulk samples of the soils and bedrock encountered in the test pits were collected for laboratory testing and to assist in strata identification. The approximated test locations are shown on Drawing 1 (Appendix B) with the AHD surface levels shown on the logs interpolated from the survey information provided by the client.

4. Assessment Results

4.1 Geology and Hydrogeology

Reference to the Canberra Geology Sheet (Ref 1) indicates that the sites are underlain by up to 5 rock units.

The western site is mapped as being underlain by 3 subgroups of the Colinton Volcanics of late Silurian age. These rock subgroups typically comprise:

- dark green dacitic ignimbrite and minor volcaniclastic sediments;
- tuffaceous shale; and
- limestone and dolomitic limestone.

The eastern site is mapped as being underlain by a subgroup of the Colinton Volcanics and two subgroups of the Cappauna Formation both of late Silurian age. These rock subgroups typically comprise:

- dark green dacitic ignimbrite and minor volcaniclastic sediments;
- shale, siltstone and minor quartzite and tuff; and
- limestone.

The field work confirmed the geological mapping with siltstone, shale and dacite encountered in those pits which intersected bedrock.

Reference to the Hydrogeology of the Australian Capital Territory and Environs Map (Ref 2) indicates that the site is located on fractured aquifers of late Silurian age. Expected geological units referred on the map include dacitic, rhyodacitic ignimbrite, bedded tuffs, minor shale, sandstone, limestone and ashstone.

Based on the hydrogeology map, the yield of aquifers increases from the east to the west from less than 0.5 l/s to 0.5 – 1.0 l/s generally around the Queanbeyan River corridor.

Total dissolved solids (TDS) are mapped as being uniform across the two sites at between 500 – 1000 mg/l.

Surface water was not observed during the site inspection with the exception of ponded water from recent rain fall. The sites are traversed by numerous intermittently flowing water courses and gully lines which run in variable directions but ultimately water flows are to the north and north west towards Jumping Creek and the Queanbeyan River.

4.2 Soil Landscape

Reference to the Canberra Soil Landscape Sheet (Ref 3) indicates both sites are mapped as being underlain by the Burra soil group.

The Burra soil group is characterised by undulating to rolling low hills and alluvial fans on Silurian Volcanics of Canberra Lowlands. Generally, waning and gently to moderately inclined hill slopes, foot slopes and fans. Soils are shallow, well drained earthy sands on crests and upper slopes, and are moderately deep, moderately well drained red podzolic soils on mid slopes and most lower slopes. Moderately deep, moderately well drained yellow podzolic soils are present along minor drainage lines and on some lower slopes. The Landscape Sheet lists this soil group as characterised by its strong acidity and low water holding capacity, its low permeability, sheet erosion risk, run-on and localised shallow soil.

4.3 Site Inspection

The principal observations noted during the site inspection are as follows:

- The site generally comprises undulating to steeply undulating undeveloped land which is moderately to heavily grassed,
- Semi-mature to mature trees are scattered across the sites,
- Weed coverage was extensive in some parts albeit appearing to have been sprayed with weed killer,
- Several locations contained dumped car bodies and scrap metal,
- Earthen mounds had been created in some areas presumably for motor bike jumps,
- Several access tracks were located on the site,
- A few areas appear to have been previously disturbed however the reason for which or total extent was difficult to determine,
- Surface cobbles and boulders and rock outcropping were observed across the entire site,
- Most of the site could be traversed on existing unsealed/unformed access tracks,
- Evidence of erosion was observed in gully lines where the natural grass and/vegetation cover has been removed,
- Minimal erosion in areas where the grass/vegetation is intact,
- With the exception of access tracks, motor bike mounds and other areas of modification mentioned above, the site is generally undisturbed,
- The flanks of the ridgelines and hills are generally moderately to steeply sloping with the ridgelines, foot slopes and gullies gently to moderately sloping in parts,
- No obvious signs of creep movements within near-surface soils were noted, nor any signs of deep-seated instability;
- No obvious signs of salinity (such as salt deposits and tree die back) or deep-seated instability within the site was observed.

4.4 Test Pit Excavation

Details of the subsurface conditions encountered are given in the test pit logs in Appendix C which must be read in conjunction with the included explanatory notes that define classification methods and terms used to describe the soils and rocks. In summary, the test pits encountered variable subsurface conditions underlying the site with the principal succession of strata broadly summarised as follows:

- TOPSOIL: silty sand and silty sandy gravel with rootlets to depths of 0.05 – 0.2 m.
- SILTY/SANDY GRAVEL: medium dense, dry to moist silty and sandy gravel with some clay in parts, in Pits 1, 4, 9, 11, 13 and 14 to depths of 0.2 – 0.7 m
- SILTY/SANDY CLAY: firm to very stiff silty and sandy clay in Pit 4 to 1.1 m depth and to the limit of investigation of 4.0 m in Pit 7.

- **SILTY SAND:** loose then dense (lightly cemented), dry to moist silty sand in Pit 7 in between two clayey layers from 0.9 m to 2.4 m depth.
- **BEDROCK:** variably extremely low to high strength, extremely to slightly weathered bedrock encountered in all pits except Pit 7 below depths of 0.05 – 1.1 m to the limit of investigation of 0.3 – 2.5 m.

A summary of the bedrock depths is provided in Table 1 below.

Table 1 – Summary of Bedrock Conditions

Pit No	Depth to Top of Rock (m)	Termination Depth (m)	Comment
1	0.2	1.6	Bucket refusal
2	0.15	1.1	Bucket refusal
3	0.2	1.4	Bucket refusal
4	1.1	2.5	Bucket refusal
5	0.05	1.4	Bucket refusal
6	0.1	0.7	Bucket refusal
7	NE	4.0	Limit of investigation
8	0.1	0.4	Bucket refusal
9	0.4	1.3	Bucket refusal
10	0.1	0.3	Bucket refusal
11	0.3	0.7	Bucket refusal
12	0.2	0.8	Bucket refusal
13	0.7	0.8	Bucket refusal
14	0.7	1.1	Bucket refusal

where: NE = Not Encountered

No free groundwater was observed during excavation of the test pits. However the pits were backfilled immediately following excavation precluding longer term monitoring of groundwater levels. Groundwater conditions rarely remain constant and can change seasonally due to variations in rainfall, temperature and soil permeability. For these reasons, it is noted that the moisture condition of the site soils may vary considerably from the time of the investigation compared to at the time of construction.

5. Laboratory Testing

Eight (8) samples collected from the test pits were tested in the laboratory for measurement of Emerson Class Number. The detailed laboratory test report sheets are given in Appendix D with the results summarised in Table 2 below.

Table 2 – Summary of Laboratory Testing

Pit No	Depth (m)	Emerson Class No	Field Description
1	0.1	8	Silty Sand
3	0.1	4	Silty Sand
4	1.0	4	Silty Sand
7	0.4	4	Sandy Clay
9	0.4	4	Sandy Gravel
12	0.1	8	Silty Sand with some gravel
13	0.1	8	Silty Sand with some gravel
14	0.5	4	Silty Clay with some gravel

The results of the laboratory testing indicate that the samples have slight to non dispersion potential.

6. Proposed Development

It is understood that the proposed development of the site is for residential purposes. The western area is understood to comprise 37 standard residential lots whilst the eastern area is to comprise 4 rural residential sized lots. At this stage design levels have not been determined however some cut and fill will be required to modify current levels for roadways.

7. Comments

7.1 General

The following comments are based on the results of site reconnaissance, review of existing information, limited fieldwork and laboratory testing and our involvement in similar projects.

It is understood that a future residential subdivision is proposed and that further investigations will be undertaken at the appropriate time as the planning and design of the subdivision proceeds. Accordingly, this report and the comments given within must be considered as being preliminary in nature.

7.2 Development Considerations

7.2.1 Site Classification

Classification of residential blocks within the site should comply with the requirements of AS 2870 – 2011 "Residential Slabs and Footings" (Ref 4). Likely lot classifications would range from Class A (sand/rock sites), Class S (slightly reactive) to Class M (moderately reactive) or Class H1/H2 (highly reactive), with the final classification dependent on soil reactivity, the presence of filling and rock depth. The topographic slope in across the eastern site ranges from intermediate to steep and accordingly, it is anticipated that these lots will need to consider design and construction techniques that take account of the ground slope and possible Class P conditions. It must be noted that some areas within blocks with steep terrain may not be considered suitable for development. Classifications within these areas would also be dependent on the extent of bulk earthworks proposed.

7.2.2 Stability Assessment

The site has been assessed with reference to the Australian Geomechanics Society Sub-Committee on Landslide Risk Management: *"Landslide Risk Management Concepts and Guidelines"* (Ref 5). Based on the observations made during the inspection, an assessment of risk to property has been undertaken for each of four distinct zones as follows:

- Zone 1: areas of gently sloping land ie: flatter than 1V:10H (vertical:horizontal) or 5 – 6°;
- Zone 2: areas of moderately sloping land ie: generally between 1V:10H and 1V:5H or 6 – 12°;
- Zone 3: areas of moderately to steeply sloping land ie: generally between 1V:5H and 1V:3.3H or 12 – 17°;
- Zone 4: areas of steeply sloping land ie: steeper than 1V:3.3H or 17°.

The results of the assessment for each of these areas are outlined in Tables 3 – 6.

Table 3 – Slope Stability Assessment – Zone 1 (Gently Sloping Areas)

Hazard	Likelihood	Consequence to Proposed Development	Risk to Proposed Development
Creep of surface soils	Barely credible	Minor	Very Low
Near surface slumping	Barely credible	Medium	Very Low
Active / deep seated slide	Barely credible	Major	Very Low

Table 4 – Slope Stability Assessment – Zone 2 (Moderately Sloping Areas)

Hazard	Likelihood	Consequence to Proposed Development	Risk to Proposed Development
Creep of surface soils	Unlikely	Minor	Low
Near surface slumping	Unlikely	Medium	Low
Active / deep seated slide	Rare	Major	Low

Table 5 – Slope Stability Assessment – Zone 3 (Moderately to Steeply Sloping Areas)

Hazard	Likelihood	Consequence to Proposed Development	Risk to Proposed Development
Failure during construction	Possible	Medium	Moderate
Creep of surface soils	Possible	Minor	Moderate
Near surface slumping	Possible	Medium	Moderate
Active / deep seated slide	Rare	Major	Low

Table 6 – Slope Stability Assessment – Zone 4 (Steeply Sloping Areas)

Hazard	Likelihood	Consequence to Proposed Development	Risk to Proposed Development
Failure during construction	Likely	Medium	High
Creep of surface soils	Likely	Minor	Moderate
Near surface slumping	Likely	Medium	High
Active / deep seated slide	Unlikely	Major	Moderate

In summary, it is considered that the western site is classified as very low risk of damage to property occurring as a result of slope instability whilst the eastern site varies from very low to high risk. Large areas of the eastern site are considered to be of moderate or high risk of causing property damage due to the steep ground slopes and possible unsuitable design and construction practice.

Notwithstanding the various risk categories nominated, development of the site for residential purposes is considered feasible in areas of gently and moderately sloping land (very low and low instability risk) with erosion control measures and suitable dwelling design to be addressed. In areas of moderately sloping land, standard practices for hillside development must be incorporated into designs.

Areas designated as moderately to steeply sloping land (low and moderate risk), could be developed for residential purposes however would have to be the subject of site and development specific geotechnical investigations to establish a site model and provide geotechnical limitations and design parameters.

Areas of steeply sloping land (moderate and high risk) are not recommended for residential development at this stage. A detailed site stability assessment including subsurface investigations must be undertaken in these areas to establish an appropriate site model for analysis purposes to assess whether development is feasible in the high risk zones.

It is noted that revisions to the above risk classifications may be necessary following completion of bulk earthworks. It is recommended that if development is proposed within the moderate and high risk areas, further delineation and assessment be undertaken.

7.2.3 Soil Erosion

It is considered that the erosion hazard within the areas proposed for development would be within accepted limits and could be managed by good engineering and land management practices which will also be required to address flood hazard and localised waterlogging limitations of soils along gully lines and low lying flat areas. These hazards are considered to impose only a minor constraint to development, on the basis they are addressed as mentioned above with good engineering and land management practice.

It is anticipated that the treatment of the existing erosion gullies as part of an overall site development would include:

- filling using select materials (i.e. non – dispersive or erodible) placed under controlled conditions;
- provision of temporary surface cover (e.g. pegged matting) during the period of valley floor revegetation;
- channel lining in sections of rapid change in gully floor grade;
- piping of flow where appropriate;
- the re-establishment of a zone of vegetation and tree cover along gully banks.

7.2.4 Footings

All footing systems for standard residential dwellings should be designed and constructed in accordance with AS 2870 – 2011 (Ref 4) for the appropriate classification. For hillside lot construction (low risk or greater), reference should be made to the publication by AGS (Ref 5), relevant extracts of which are included in Appendix E.

For preliminary sizing of footings, allowable base bearing pressures for the various strata likely to be encountered including controlled filling are given below:

- | | |
|---|----------|
| • Stiff or loose to medium dense natural soils: | 100 kPa |
| • Controlled Filling: | 150 kPa |
| • Very stiff or medium dense natural soils: | 150 kPa |
| • Extremely low and very low strength bedrock: | 500 kPa |
| • Low strength bedrock: | 1000 kPa |

7.3 Site Preparation and Earthworks

7.3.1 Stripping

Site preparation for the construction of roadways and structures should include the removal of vegetation, topsoils, silty sandy soils, existing filling and other deleterious materials from the proposed building areas. Deep excavations (such as in gullies) could occur should localised deeper topsoils or

unsuitable materials/filling be encountered, if inclement weather precedes construction or if the contractor adopts inappropriate stripping methods.

It is expected that the site is underlain at least in parts by silty sands/sandy silts (beneath the topsoils). This material is usually difficult to handle and compact and would require extremely careful moisture control. It is recommended that allowance be made for at least partial stripping of this material (say 0.3 m following topsoil stripping), with inspection undertaken by a suitably qualified geotechnical engineer to assess the depth of removal required at the time of construction. Where possible (ie: in deep fill areas) this material could be designated to remain insitu, however if considered unsuitable would be required to be removed. Also, if stripping of the silty material is needed, it be limited to 0.4 m only as it is unlikely to improve with depth. The excavated material should be replaced with a granular bridging layer.

Depending on prior weather conditions it may also be necessary to use a geofabric separation layer.

7.3.2 Excavation Conditions

It is expected that the subsurface profile will comprise a variable soil profile underlain by bedrock which in parts may be of very high to extremely high strength.

The site soils and weathered bedrock up to low strength could be expected to be removed using conventional large earthmoving plant. The presence of outcropping rock or boulders at the surface may preclude effective use of scrapers in some areas.

Excavation of the bedrock will largely be dependent on the degree of fracturing/jointing and the strike and dip of bedding within the rock relative to the excavation. Depending on excavation depths, heavy ripping or heavy rock hammering may be required but would have low production rates; blasting would be recommended to further fracture the bedrock to expedite ripping activities.

The extent of groundwater inflow would be dependent on prior weather conditions. Given the extent of gully lines and relatively flat topography over some parts of the site, groundwater seepages should be anticipated, which would increase following rainfall. Groundwater springs may also arise following stripping and excavation works.

7.3.3 Filling Placement

In areas that require filling, the stripped surfaces must be test rolled in the presence of a geotechnical engineer. Any areas exhibiting significant deflections under test rolling must be appropriately treated by over-excavation and replacement with suitable non-reactive filling. All filling material must be placed in horizontal layers of maximum 250 mm loose thickness. The material must have a moisture content within the range of $\pm 2\%$ of modified optimum at the time of placement.

All permanent fill batters must be constructed no steeper than 1:3 (vertical:horizontal), appropriately protected against erosion with toe and spoon drains constructed as a means of controlling surface flows on the batters and vegetation of the batter.

7.3.4 Filling Compaction

All filling placed within construction platforms must be compacted to a minimum 90% modified maximum dry density, except for the upper 1.0 m within pavement areas, which must be compacted to a minimum of 95% modified maximum dry density.

To validate future site classifications, field inspections and in-situ testing of future earthworks must be undertaken on any controlled filling placed in residential blocks in order to satisfy the requirements of a Level 1 inspection and testing service as defined in AS 3798 – 2007 (Ref 6).

7.4 Drainage

Parts of the site have poor natural subsurface drainage. Infiltrated rainwater can become contained in the upper semi-pervious silty/sandy stratum and deeper sandy/gravelly layers. Seepage water may also enter fractures in the bedrock at locations where the bedrock outcrops or is at shallow depth. Seepage water in the subsurface profile may rise to the ground surface further downslope as springs.

In order to reduce the downslope seepage flow volume into residential areas, it is recommended that:

- An open unlined, contour drain be constructed along the upslope boundary of the development areas extending to at least 0.5 m depth below the bedrock surface;
- Floodways be constructed along natural drainage lines;
- Deep subsurface gravel drains to be installed along the invert of major gullies to be infilled and through any spring areas;
- Subsurface drains be installed along both sides of roads constructed in cut and/or at about natural grade. Some sections of road subgrades may need to be provided with cross-drains or a drainage blanket to control upward seepages.

7.5 House Site Maintenance

The developed blocks should be maintained in accordance with the CSIRO publication "Guide to Home Owners on Foundation Maintenance and Footing Performance", a copy of which is included in Appendix F. Whilst it must be accepted that minor cracking in most structures is inevitable, the guide describes suggested site maintenance practices aimed at minimising foundation movement to keep cracking within acceptable limits. Surface drainage should be installed and maintained at the site. All collected stormwater, groundwater and roof runoff should be discharged into the stormwater disposal system.

7.6 Pavements

Whilst subsurface investigations along roadways and design of pavements have yet to be undertaken, based on the results of the site inspection and previous experience in the nearby area, Table 7 gives indicative design CBR values for the various likely subgrade conditions.

Table 7 – Design CBR Values

Subgrade Material	Design CBR (%)
Clay (high plasticity)	1 – 2
Sandy/Gravelly Soils	3 – 4
Recompacted (sedimentary) Weathered Rock	3 – 5
Recompacted (Igneous) Weathered Rock	5 – 7
Insitu Weathered Rock	7 – 10

There may be construction advantages in undertaking subgrade replacement in those areas where any high plasticity clay subgrades occur. Detailed investigations will be required following finalisation of subdivision layout to confirm and delineate, if possible the variation in subgrade conditions. Surface and subsurface drainage must be installed and maintained to protect the pavement and subgrade. The subsurface drains should extend a minimum of 0.5 m depth below the subgrade level.

7.7 Salinity

No visual signs of salinity were observed during the site inspection. It is suggested as part of future detailed investigations that some samples be collected of site soils for laboratory testing of electrical conductivity and pH values to enable further screening comment to be made on salinity. It is envisaged that a full salinity assessment is not required given the lack of supporting evidence on this site and surrounding parts of Queanbeyan for significant salinity issues.

7.8 Development Constraints

The assessment has identified a number of constraints on the development, which are:

- Potential for waterlogging in several areas including spring activity;
- Potential for erosion in areas where vegetation cover is removed;
- Areas of moderate and high risk of damage to property with respect to slope instability;
- Uncontrolled filling associated with tracks, mounds and fly tipping (car bodies);
- Outcropping and shallow very high strength bedrock.

Waterlogging: There is evidence of previous wet, soft and/or boggy conditions within several areas identified as potential for waterlogging. These areas are characterised by slightly greener grass and contain grass species which from Douglas Partners experience indicates previous or current presence of elevated soil/ground water levels. They appear to be limited to gully lines.

Erosion: Where the previous vegetation cover has been removed, which is mostly in gully lines and disturbed areas, evidence of erosion ranging from slight to severe was observed.

Stability: A large portion of the eastern site has been assessed as having a potential moderate to high risk of damage to property from land instability.

Uncontrolled Filling: Removal of uncontrolled fill can be included as part of the site regrading or site clean-up during construction of the development and would only pose a minor constraint to development.

High Strength Bedrock: The presence of outcrops and shallow very high strength bedrock would prove difficult to excavate should design levels require cutting.

After the above constraints are addressed, the site would be considered suitable for the proposed development.

7.9 Remedial Measures/Site Controls

The main activities or methods to enable effective development of the site, from a geotechnical perspective, would be:

- planning/layout of development areas,
- extensive drainage measures,
- erosion management,
- timing of works,
- development restrictions from a slope instability perspective;
- minimising cut-fill on hillside;

7.9.1 Planning/Layout of Development

Gully lines and possibly low lying areas should be avoided for standard residential construction without engineering modification as these areas would require extensive drainage works and/or bulk earthworks. Where possible, roads should be positioned over the top of gully lines to enable the construction of subsurface drainage lines. If development of the low lying areas is being considered, controlled filling would be required to raise surface levels to assist in drainage design. Should residential areas be proposed over drainage areas, Class P site classifications would be warranted with special advice required on foundation design and construction as not to interfere with the drainage measures.

7.9.2 Drainage Measures

Engineered drainage both to divert overland flow and intercept subsurface flow combined with bulk earthworks to raise surface levels and or contour the surface level to improve drainage will be required if permanent structures are to be constructed in gully and/or low lying areas.

A network of drainage lines would be required across the sites to intercept and provide a controlled transportation pathway for groundwater flows. Main drainage lines would be located at the base of

gullies and within the low lying areas with interceptor drainage lines constructed as and where required across the site feeding into the main drainage lines. The drainage lines could either be subsurface or surface (floodway) type structures depending on surface levels.

7.9.3 Erosion Management

One of the existing limitations to development of the site is considered to be areas of gully erosion. Soil and water management is an integral part of the development process and should adopt a preventative rather than a reactive approach to the site limitations, such that the work can proceed without undue pollution of receiving streams.

A detailed soil and water management plan (SWMP) will be required and should be incorporated into the engineering design of the development methods for:

- minimising water pollution due to erosion of soils or the development of saline conditions;
- minimisation of soil erosion during and after construction;
- maximising the re-use of materials on site.

7.9.4 Timing of Works

Timing of the site works could also be a critical aspect that will require careful consideration. Bulk earthworks activities is suggested to be undertaken in the warmer months of the year and not the winter months when ground moisture is higher due to the negative evapotranspiration effect experienced in winter. If moist soils are encountered and require drying to enable reuse in controlled filling areas, the warmer months would allow more expedited processing negating the potential for several weeks of drying time expected during winter.

7.9.5 Development Restrictions

Development within areas of medium risk of instability is technically feasible though would be required to be undertaken with geotechnical guidance. Site specific and development specific geotechnical investigation and advice would be required for individual structures.

At this stage without subsurface investigations, development within the high risk areas are not recommended. A comprehensive site stability assessment will be required if development in those areas are proposed.

7.9.6 Cut – Fill Minimisation on Hillside

It is standard hillside development practice to minimise the depths of cutting and filling though feasible to undertake significant works with geotechnical approval and guidance. All proposed modification of the ground slope in hillside areas must be subject to geotechnical review and comment.

7.10 Subsurface Investigations

Detailed subsurface investigation and laboratory testing will be required as the conceptual design/planning progresses, and during the design and construction phases. Specific investigation would include but not necessarily be limited to:

- Detailed geotechnical investigation and assessment of areas of steeply sloping land should development be desired in these areas, and
- Detailed geotechnical investigation on a stage by stage basis as development proceeds to determine excavation conditions and support, road subgrade CBR values and confirm site classifications for each lot.

7.11 Summary

The site assessment undertaken as described above has indicated that the majority of the site is suitable from a geotechnical perspective for residential development. Comments have been given on the various geotechnical aspects of the proposed development and the identified development constraints and subsequent remedial and control measures. Conceptual comments on design and construction aspects are also given in the report. Further testing and assessment will be required as the design of the subdivision proceeds and as such, this report must be considered as being preliminary in nature.

8. References

1. Geology of Canberra 1:100 000 Geological Series Sheet 8727, Bureau of Mineral Resources, (1992).
2. Bureau of Mineral Resources, Geology and Geophysics (1984): 'Hydrogeology of the Australian Capital Territory and Environs' 1:100,000 scale map.
3. Soil Landscape of Canberra 1:100 000 Soil Landscape Series Sheet 8727, NSW Dept of Land and Water Conservation, (2000).
4. Australian Standard AS 2870 – 2011 Residential Slabs and Footings.
5. AGS – Landslide Risk Management Concepts and Guidelines, Australian Geomechanics Society, Sub-committee on Landslide Risk Management, 2007.
6. Australian Standard AS 3798 – 2007 Guidelines on Earthworks for Commercial and Residential Developments.

9. Limitations

Douglas Partners (DP) has prepared this report for the deferred areas within Stage 3 of the proposed Jumping Creek development in Queanbeyan as described within this report. This report is provided for the exclusive use of CIC Australia Ltd for this project only and for the purposes as described in the report. It should not be used by or relied upon for other projects or purposes on the same or other site or by a third party. Any party so relying upon this report beyond its exclusive use and purpose as stated above, and without the express written consent of DP, does so entirely at its own risk and without recourse to DP for any loss or damage. In preparing this report DP has necessarily relied upon information provided by the client and/or their agents.

The results provided in the report are indicative of the sub-surface conditions only at the specific sampling or testing locations, and then only to the depths investigated and at the time the work was carried out. Sub-surface conditions can change abruptly due to variable geological processes and also as a result of anthropogenic influences. Such changes may occur after DP's field testing has been completed.

DP's advice is based upon the conditions encountered during this investigation. The accuracy of the advice provided by DP in this report may be limited by undetected variations in ground conditions between sampling locations. The advice may also be limited by budget constraints imposed by others or by site accessibility.

This report must be read in conjunction with all of the attached notes and should be kept in its entirety without separation of individual pages or sections. DP cannot be held responsible for interpretations or conclusions made by others unless they are supported by an expressed statement, interpretation, outcome or conclusion given in this report.

This report, or sections from this report, should not be used as part of a specification for a project, without review and agreement by DP. This is because this report has been written as advice and opinion rather than instructions for construction.

The contents of this report do not constitute formal design components such as are required, by the Health and Safety Legislation and Regulations, to be included in a Safety Report specifying the hazards likely to be encountered during construction and the controls required to mitigate risk. This design process requires risk assessment to be undertaken, with such assessment being dependent upon factors relating to likelihood of occurrence and consequences of damage to property and to life. This, in turn, requires project data and analysis presently beyond the knowledge and project role respectively of DP. DP may be able, however, to assist the client in carrying out a risk assessment of potential hazards contained in the Comments section of this report, as an extension to the current scope of works, if so requested, and provided that suitable additional information is made available to DP. Any such risk assessment would, however, be necessarily restricted to the geotechnical and groundwater components set out in this report and to their application by the project designers to project design, construction, maintenance and demolition.

Douglas Partners Pty Ltd

Appendix A

About this Report

About this Report

Douglas Partners



Introduction

These notes have been provided to amplify DP's report in regard to classification methods, field procedures and the comments section. Not all are necessarily relevant to all reports.

DP's reports are based on information gained from limited subsurface excavations and sampling, supplemented by knowledge of local geology and experience. For this reason, they must be regarded as interpretive rather than factual documents, limited to some extent by the scope of information on which they rely.

Copyright

This report is the property of Douglas Partners Pty Ltd. The report may only be used for the purpose for which it was commissioned and in accordance with the Conditions of Engagement for the commission supplied at the time of proposal. Unauthorised use of this report in any form whatsoever is prohibited.

Borehole and Test Pit Logs

The borehole and test pit logs presented in this report are an engineering and/or geological interpretation of the subsurface conditions, and their reliability will depend to some extent on frequency of sampling and the method of drilling or excavation. Ideally, continuous undisturbed sampling or core drilling will provide the most reliable assessment, but this is not always practicable or possible to justify on economic grounds. In any case the boreholes and test pits represent only a very small sample of the total subsurface profile.

Interpretation of the information and its application to design and construction should therefore take into account the spacing of boreholes or pits, the frequency of sampling, and the possibility of other than 'straight line' variations between the test locations.

Groundwater

Where groundwater levels are measured in boreholes there are several potential problems, namely:

- In low permeability soils groundwater may enter the hole very slowly or perhaps not at all during the time the hole is left open;

- A localised, perched water table may lead to an erroneous indication of the true water table;
- Water table levels will vary from time to time with seasons or recent weather changes. They may not be the same at the time of construction as are indicated in the report; and
- The use of water or mud as a drilling fluid will mask any groundwater inflow. Water has to be blown out of the hole and drilling mud must first be washed out of the hole if water measurements are to be made.

More reliable measurements can be made by installing standpipes which are read at intervals over several days, or perhaps weeks for low permeability soils. Piezometers, sealed in a particular stratum, may be advisable in low permeability soils or where there may be interference from a perched water table.

Reports

The report has been prepared by qualified personnel, is based on the information obtained from field and laboratory testing, and has been undertaken to current engineering standards of interpretation and analysis. Where the report has been prepared for a specific design proposal, the information and interpretation may not be relevant if the design proposal is changed. If this happens, DP will be pleased to review the report and the sufficiency of the investigation work.

Every care is taken with the report as it relates to interpretation of subsurface conditions, discussion of geotechnical and environmental aspects, and recommendations or suggestions for design and construction. However, DP cannot always anticipate or assume responsibility for:

- Unexpected variations in ground conditions. The potential for this will depend partly on borehole or pit spacing and sampling frequency;
- Changes in policy or interpretations of policy by statutory authorities; or
- The actions of contractors responding to commercial pressures.

If these occur, DP will be pleased to assist with investigations or advice to resolve the matter.

About this Report

Site Anomalies

In the event that conditions encountered on site during construction appear to vary from those which were expected from the information contained in the report, DP requests that it be immediately notified. Most problems are much more readily resolved when conditions are exposed rather than at some later stage, well after the event.

Information for Contractual Purposes



Where information obtained from this report is provided for tendering purposes, it is recommended that all information, including the written report and discussion, be made available. In circumstances where the discussion or comments section is not relevant to the contractual situation, it may be appropriate to prepare a specially edited document. DP would be pleased to assist in this regard and/or to make additional report copies available for contract purposes at a nominal charge.

Site Inspection

The company will always be pleased to provide engineering inspection services for geotechnical and environmental aspects of work to which this report is related. This could range from a site visit to confirm that conditions exposed are as expected, to full time engineering presence on site.

Appendix B

Drawing 1



Locality Plan

LEGEND

-  Extent of Deferred Areas
-  Approximate Test Pit Location

NOTE: Base image provided by Google Earth 2015

<div>Douglas Partners <small>Geotechnics Environment Groundwater</small></div>		CLIENT: CIC Australia Ltd		TITLE: Test Location Plan	
OFFICE: Canberra		DRAWN BY: APH		Proposed Subdivision - Deferred Areas	
SCALE: NTS		DATE: 4.08.2015		Stage 3 Jumping Creek, Queanbeyan	
		PROJECT No: 88224.00		DRAWING No: 1	
				REVISION: 0	

Appendix C

Explanatory Notes
Results of Field Work (Pits 1 – 14)



Sampling

Sampling is carried out during drilling or test pitting to allow engineering examination (and laboratory testing where required) of the soil or rock.

Disturbed samples taken during drilling provide information on colour, type, inclusions and, depending upon the degree of disturbance, some information on strength and structure.

Undisturbed samples are taken by pushing a thin-walled sample tube into the soil and withdrawing it to obtain a sample of the soil in a relatively undisturbed state. Such samples yield information on structure and strength, and are necessary for laboratory determination of shear strength and compressibility. Undisturbed sampling is generally effective only in cohesive soils.

Test Pits

Test pits are usually excavated with a backhoe or an excavator, allowing close examination of the in-situ soil if it is safe to enter into the pit. The depth of excavation is limited to about 3 m for a backhoe and up to 6 m for a large excavator. A potential disadvantage of this investigation method is the larger area of disturbance to the site.

Large Diameter Augers

Boreholes can be drilled using a rotating plate or short spiral auger, generally 300 mm or larger in diameter commonly mounted on a standard piling rig. The cuttings are returned to the surface at intervals (generally not more than 0.5 m) and are disturbed but usually unchanged in moisture content. Identification of soil strata is generally much more reliable than with continuous spiral flight augers, and is usually supplemented by occasional undisturbed tube samples.

Continuous Spiral Flight Augers

The borehole is advanced using 90-115 mm diameter continuous spiral flight augers which are withdrawn at intervals to allow sampling or in-situ testing. This is a relatively economical means of drilling in clays and sands above the water table. Samples are returned to the surface, or may be collected after withdrawal of the auger flights, but they are disturbed and may be mixed with soils from the sides of the hole. Information from the drilling (as distinct from specific sampling by SPTs or undisturbed samples) is of relatively low

reliability, due to the remoulding, possible mixing or softening of samples by groundwater.

Non-core Rotary Drilling

The borehole is advanced using a rotary bit, with water or drilling mud being pumped down the drill rods and returned up the annulus, carrying the drill cuttings. Only major changes in stratification can be determined from the cuttings, together with some information from the rate of penetration. Where drilling mud is used this can mask the cuttings and reliable identification is only possible from separate sampling such as SPTs.

Continuous Core Drilling

A continuous core sample can be obtained using a diamond tipped core barrel, usually with a 50 mm internal diameter. Provided full core recovery is achieved (which is not always possible in weak rocks and granular soils), this technique provides a very reliable method of investigation.

Standard Penetration Tests

Standard penetration tests (SPT) are used as a means of estimating the density or strength of soils and also of obtaining a relatively undisturbed sample. The test procedure is described in Australian Standard 1289, Methods of Testing Soils for Engineering Purposes - Test 6.3.1.

The test is carried out in a borehole by driving a 50 mm diameter split sample tube under the impact of a 63 kg hammer with a free fall of 760 mm. It is normal for the tube to be driven in three successive 150 mm increments and the 'N' value is taken as the number of blows for the last 300 mm. In dense sands, very hard clays or weak rock, the full 450 mm penetration may not be practicable and the test is discontinued.

The test results are reported in the following form.

- In the case where full penetration is obtained with successive blow counts for each 150 mm of, say, 4, 6 and 7 as:
4,6,7
N=13
- In the case where the test is discontinued before the full penetration depth, say after 15 blows for the first 150 mm and 30 blows for the next 40 mm as:
15, 30/40 mm

Sampling Methods

The results of the SPT tests can be related empirically to the engineering properties of the soils.

Dynamic Cone Penetrometer Tests / Perth Sand Penetrometer Tests

Dynamic penetrometer tests (DCP or PSP) are carried out by driving a steel rod into the ground using a standard weight of hammer falling a specified distance. As the rod penetrates the soil the number of blows required to penetrate each successive 150 mm depth are recorded. Normally there is a depth limitation of 1.2 m, but this may be extended in certain conditions by the use of extension rods. Two types of penetrometer are commonly used.

- Perth sand penetrometer - a 16 mm diameter flat ended rod is driven using a 9 kg hammer dropping 600 mm (AS 1289, Test 6.3.3). This test was developed for testing the density of sands and is mainly used in granular soils and filling.
- Cone penetrometer - a 16 mm diameter rod with a 20 mm diameter cone end is driven using a 9 kg hammer dropping 510 mm (AS 1289, Test 6.3.2). This test was developed initially for pavement subgrade investigations, and correlations of the test results with California Bearing Ratio have been published by various road authorities.



Description and Classification Methods

The methods of description and classification of soils and rocks used in this report are based on Australian Standard AS 1726, Geotechnical Site Investigations Code. In general, the descriptions include strength or density, colour, structure, soil or rock type and inclusions.

Soil Types

Soil types are described according to the predominant particle size, qualified by the grading of other particles present:

Type	Particle size (mm)
Boulder	>200
Cobble	63 - 200
Gravel	2.36 - 63
Sand	0.075 - 2.36
Silt	0.002 - 0.075
Clay	<0.002

The sand and gravel sizes can be further subdivided as follows:

Type	Particle size (mm)
Coarse gravel	20 - 63
Medium gravel	6 - 20
Fine gravel	2.36 - 6
Coarse sand	0.6 - 2.36
Medium sand	0.2 - 0.6
Fine sand	0.075 - 0.2

The proportions of secondary constituents of soils are described as:

Term	Proportion	Example
And	Specify	Clay (60%) and Sand (40%)
Adjective	20 - 35%	Sandy Clay
Slightly	12 - 20%	Slightly Sandy Clay
With some	5 - 12%	Clay with some sand
With a trace of	0 - 5%	Clay with a trace of sand

Definitions of grading terms used are:

- Well graded - a good representation of all particle sizes
- Poorly graded - an excess or deficiency of particular sizes within the specified range
- Uniformly graded - an excess of a particular particle size
- Gap graded - a deficiency of a particular particle size with the range

Cohesive Soils

Cohesive soils, such as clays, are classified on the basis of undrained shear strength. The strength may be measured by laboratory testing, or estimated by field tests or engineering examination. The strength terms are defined as follows:

Description	Abbreviation	Undrained shear strength (kPa)
Very soft	vs	<12
Soft	s	12 - 25
Firm	f	25 - 50
Stiff	st	50 - 100
Very stiff	vst	100 - 200
Hard	h	>200

Cohesionless Soils

Cohesionless soils, such as clean sands, are classified on the basis of relative density, generally from the results of standard penetration tests (SPT), cone penetration tests (CPT) or dynamic penetrometers (PSP). The relative density terms are given below:

Relative Density	Abbreviation	SPT N value	CPT qc value (MPa)
Very loose	vl	<4	<2
Loose	l	4 - 10	2 - 5
Medium dense	md	10 - 30	5 - 15
Dense	d	30 - 50	15 - 25
Very dense	vd	>50	>25

Soil Descriptions

Soil Origin

It is often difficult to accurately determine the origin of a soil. Soils can generally be classified as:

- Residual soil - derived from in-situ weathering of the underlying rock;
- Transported soils - formed somewhere else and transported by nature to the site; or
- Filling - moved by man.

Transported soils may be further subdivided into:

- Alluvium - river deposits
- Lacustrine - lake deposits
- Aeolian - wind deposits
- Littoral - beach deposits
- Estuarine - tidal river deposits
- Talus - scree or coarse colluvium
- Slopewash or Colluvium - transported downslope by gravity assisted by water. Often includes angular rock fragments and boulders.



Rock Strength

Rock strength is defined by the Point Load Strength Index ($IS_{(50)}$) and refers to the strength of the rock substance and not the strength of the overall rock mass, which may be considerably weaker due to defects. The test procedure is described by Australian Standard 4133.4.1 - 1993. The terms used to describe rock strength are as follows:

Term	Abbreviation	Point Load Index $IS_{(50)}$ MPa	Approx Unconfined Compressive Strength MPa*
Extremely low	EL	<0.03	<0.6
Very low	VL	0.03 - 0.1	0.6 - 2
Low	L	0.1 - 0.3	2 - 6
Medium	M	0.3 - 1.0	6 - 20
High	H	1 - 3	20 - 60
Very high	VH	3 - 10	60 - 200
Extremely high	EH	>10	>200

* Assumes a ratio of 20:1 for UCS to $IS_{(50)}$

Degree of Weathering

The degree of weathering of rock is classified as follows:

Term	Abbreviation	Description
Extremely weathered	EW	Rock substance has soil properties, i.e. it can be remoulded and classified as a soil but the texture of the original rock is still evident.
Highly weathered	HW	Limonite staining or bleaching affects whole of rock substance and other signs of decomposition are evident. Porosity and strength may be altered as a result of iron leaching or deposition. Colour and strength of original fresh rock is not recognisable
Moderately weathered	MW	Staining and discolouration of rock substance has taken place
Slightly weathered	SW	Rock substance is slightly discoloured but shows little or no change of strength from fresh rock
Fresh stained	Fs	Rock substance unaffected by weathering but staining visible along defects
Fresh	Fr	No signs of decomposition or staining

Degree of Fracturing

The following classification applies to the spacing of natural fractures in diamond drill cores. It includes bedding plane partings, joints and other defects, but excludes drilling breaks.

Term	Description
Fragmented	Fragments of <20 mm
Highly Fractured	Core lengths of 20-40 mm with some fragments
Fractured	Core lengths of 40-200 mm with some shorter and longer sections
Slightly Fractured	Core lengths of 200-1000 mm with some shorter and longer sections
Unbroken	Core lengths mostly > 1000 mm

Rock Descriptions

Rock Quality Designation

The quality of the cored rock can be measured using the Rock Quality Designation (RQD) index, defined as:

$$\text{RQD \%} = \frac{\text{cumulative length of 'sound' core sections} \geq 100 \text{ mm long}}{\text{total drilled length of section being assessed}}$$

where 'sound' rock is assessed to be rock of low strength or better. The RQD applies only to natural fractures. If the core is broken by drilling or handling (i.e. drilling breaks) then the broken pieces are fitted back together and are not included in the calculation of RQD.

Stratification Spacing

For sedimentary rocks the following terms may be used to describe the spacing of bedding partings:

Term	Separation of Stratification Planes
Thinly laminated	< 6 mm
Laminated	6 mm to 20 mm
Very thinly bedded	20 mm to 60 mm
Thinly bedded	60 mm to 0.2 m
Medium bedded	0.2 m to 0.6 m
Thickly bedded	0.6 m to 2 m
Very thickly bedded	> 2 m

Symbols & Abbreviations

Douglas Partners



Introduction

These notes summarise abbreviations commonly used on borehole logs and test pit reports.

Drilling or Excavation Methods

C	Core Drilling
R	Rotary drilling
SFA	Spiral flight augers
NMLC	Diamond core - 52 mm dia
NQ	Diamond core - 47 mm dia
HQ	Diamond core - 63 mm dia
PQ	Diamond core - 81 mm dia

Water

▷	Water seep
▽	Water level

Sampling and Testing

A	Auger sample
B	Bulk sample
D	Disturbed sample
E	Environmental sample
U ₅₀	Undisturbed tube sample (50mm)
W	Water sample
pp	pocket penetrometer (kPa)
PID	Photo ionisation detector
PL	Point load strength Is(50) MPa
S	Standard Penetration Test
V	Shear vane (kPa)

Description of Defects in Rock

The abbreviated descriptions of the defects should be in the following order: Depth, Type, Orientation, Coating, Shape, Roughness and Other. Drilling and handling breaks are not usually included on the logs.

Defect Type

B	Bedding plane
Cs	Clay seam
Cv	Cleavage
Cz	Crushed zone
Ds	Decomposed seam
F	Fault
J	Joint
Lam	lamination
Pt	Parting
Sz	Sheared Zone
V	Vein

Orientation

The inclination of defects is always measured from the perpendicular to the core axis.

h	horizontal
v	vertical
sh	sub-horizontal
sv	sub-vertical

Coating or Infilling Term

cln	clean
co	coating
he	healed
inf	infilled
stn	stained
ti	tight
vn	veneer

Coating Descriptor

ca	calcite
cbs	carbonaceous
cly	clay
fe	iron oxide
mn	manganese
slt	silty

Shape

cu	curved
ir	irregular
pl	planar
st	stepped
un	undulating

Roughness

po	polished
ro	rough
sl	slickensided
sm	smooth
vr	very rough

Other

fg	fragmented
bnd	band
qtz	quartz

Symbols & Abbreviations

Graphic Symbols for Soil and Rock

General



Asphalt



Road base



Concrete



Filling


Soils




Topsoil




Peat



Clay



Silty clay



Sandy clay



Gravelly clay



Shaly clay




Silt




Clayey silt




Sandy silt



Sand



Clayey sand




Silty sand



Gravel



Sandy gravel




Cobbles, boulders



Talus

Sedimentary Rocks




Boulder conglomerate



Conglomerate




Conglomeratic sandstone




Sandstone



Siltstone




Laminite



Mudstone, claystone, shale




Coal




Limestone


Metamorphic Rocks



Slate, phyllite, schist




Gneiss




Quartzite


Igneous Rocks




Granite



Dolerite, basalt, andesite



Dacite, epidote



Tuff, breccia



Porphyry

TEST PIT LOG

CLIENT: CIC Australia Ltd
PROJECT: Proposed Subdivision - Deferred Areas
LOCATION: Stage 3 Jumping Creek, Queanbeyan

SURFACE LEVEL: 614.5 AHD
EASTING:
NORTHING:

PIT No: 1
PROJECT No: 88224.00
DATE: 17/8/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
614	0.05	TOPSOIL - moist, brown, fine to coarse grained silty sand with rootlets		D	0.1							
	0.2	SANDY SILTY GRAVEL - dry to moist, brown/light brown, fine to coarse grained sandy silty gravel with shale cobbles										
		SHALE - extremely low strength, highly weathered, yellow brown shale		D	0.5							
		- from 0.8m low strength, highly weathered, orange/brown, fine to coarse grained, highly fractured, clay seams		D	1.0							
613		- from 1.3m low to medium strength, highly weathered, yellow/brown, highly fractured		D	1.5							
1.6		Pit discontinued at 1.6m - bucket refusal										
2												
612												
3												
611												
4												
610												

RIG: Kubota KX057-4 mini excavator

LOGGED: APH

SURVEY DATUM: MGA94

WATER OBSERVATIONS: No free groundwater observed

REMARKS:

☐ Sand Penetrometer AS1289.6.3.3
☐ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND					
A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	▷	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

TEST PIT LOG

CLIENT: CIC Australia Ltd
PROJECT: Proposed Subdivision - Deferred Areas
LOCATION: Stage 3 Jumping Creek, Queanbeyan

SURFACE LEVEL: 604 AHD
EASTING:
NORTHING:

PIT No: 2
PROJECT No: 88224.00
DATE: 17/8/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
604	0.15	TOPSOIL - moist, brown, fine to coarse grained silty sand with rootlets		D	0.1							
		SHALE - low to medium strength, moderately to highly weathered, dry to moist, red/brown, fine to coarse grained, highly fractured shale		B	0.4							
					0.6							
		- from 0.65m medium to high strength, yellow/grey/brown, highly fractured		D	1.0							
603	1.1	Pit discontinued at 1.1m - bucket refusal										
602	2											
601	3											
600	4											

RIG: Kubota KX057-4 mini excavator

LOGGED: APH

SURVEY DATUM: MGA94

WATER OBSERVATIONS: No free groundwater observed

REMARKS:

- ☐ Sand Penetrometer AS1289.6.3.3
☐ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND					
A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	▷	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

TEST PIT LOG

CLIENT: CIC Australia Ltd
PROJECT: Proposed Subdivision - Deferred Areas
LOCATION: Stage 3 Jumping Creek, Queanbeyan

SURFACE LEVEL: 595 AHD
EASTING:
NORTHING:

PIT No: 3
PROJECT No: 88224.00
DATE: 17/8/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
595	0.2	TOPSOIL - moist, brown, fine to coarse grained silty sand with rootlets		D	0.1							
		SHALE - low to medium strength, red/brown, fine to coarse grained shale, with clay seams		B	0.4							
		- from 0.7m medium strength, moderately weathered			0.6							
594	1	- from 1.1m high strength, slightly weathered, brown/grey		D	1.0							
	1.4	Pit discontinued at 1.4m - bucket refusal		D	1.4							
593	2											
592	3											
591	4											

RIG: Kubota KX057-4 mini excavator

LOGGED: APH

SURVEY DATUM: MGA94

WATER OBSERVATIONS: No free groundwater observed

REMARKS:

- ☐ Sand Penetrometer AS1289.6.3.3
☐ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND					
A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	▷	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

TEST PIT LOG

CLIENT: CIC Australia Ltd
PROJECT: Proposed Subdivision - Deferred Areas
LOCATION: Stage 3 Jumping Creek, Queanbeyan

SURFACE LEVEL: 589 AHD
EASTING:
NORTHING:

PIT No: 4
PROJECT No: 88224.00
DATE: 17/8/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
589	0.1	TOPSOIL - moist, brown, fine to coarse grained silty sand with rootlets		D	0.1		pp = 100-120					
	0.3	SILTY GRAVELLY SAND - medium dense, dry to moist, fine to medium grained silty gravelly sand										
		SILTY CLAY - firm, dry to moist, red/brown, medium plasticity silty clay, with trace of cobbles		B	0.4							
					0.6							
588	1			D	1.0							
	1.1	SILTSTONE - moderately to slightly weathered, blue/grey, highly fractured, medium grained siltstone										
		- from 1.5m medium to high strength, slightly weathered, highly fractured		D	1.5							
587	2			D	2.0							
				D	2.5							
	2.5	Pit discontinued at 2.5m - bucket refusal		D	2.5							
586	3											
585	4											

RIG: Kubota KX057-4 mini excavator

LOGGED: APH

SURVEY DATUM: MGA94

WATER OBSERVATIONS: No free groundwater observed

REMARKS:

- ☐ Sand Penetrometer AS1289.6.3.3
☐ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND					
A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)

TEST PIT LOG

CLIENT: CIC Australia Ltd
PROJECT: Proposed Subdivision - Deferred Areas
LOCATION: Stage 3 Jumping Creek, Queanbeyan

SURFACE LEVEL: 604 AHD
EASTING:
NORTHING:

PIT No: 5
PROJECT No: 88224.00
DATE: 17/8/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
604	0.05	TOPSOIL - moist, brown, fine to coarse grained silty sand with rootlets SHALE - high strength, moderately weathered, grey, highly fractured shale		D	0.1							
				D	0.5							
603	1			D	1.0							
	1.4	Pit discontinued at 1.4m - bucket refusal		D	1.4							
602	2											
601	3											
600	4											

RIG: Kubota KX057-4 mini excavator

LOGGED: APH

SURVEY DATUM: MGA94

WATER OBSERVATIONS: No free groundwater observed

REMARKS:

- ☐ Sand Penetrometer AS1289.6.3.3
☐ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND					
A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	▷	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

TEST PIT LOG

CLIENT: CIC Australia Ltd
PROJECT: Proposed Subdivision - Deferred Areas
LOCATION: Stage 3 Jumping Creek, Queanbeyan

SURFACE LEVEL: 598 AHD
EASTING:
NORTHING:

PIT No: 6
PROJECT No: 88224.00
DATE: 17/8/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
598	0.1	TOPSOIL - moist to wet, brown silty sandy gravel with rootlets and some cobbles		D	0.1							
		SHALE - medium to high strength, dark brown/grey, fine to coarse grained, highly fractured shale		D	0.5							
		- from 0.4m high strength, slightly weathered, grey		D	0.7							
	0.7	Pit discontinued at 0.7m - bucket refusal										
597	1											
596	2											
595	3											
594	4											

RIG: Kubota KX057-4 mini excavator

LOGGED: APH

SURVEY DATUM: MGA94

WATER OBSERVATIONS: No free groundwater observed

REMARKS:

- ☐ Sand Penetrometer AS1289.6.3.3
☐ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND					
A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	▷	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

TEST PIT LOG

CLIENT: CIC Australia Ltd
PROJECT: Proposed Subdivision - Deferred Areas
LOCATION: Stage 3 Jumping Creek, Queanbeyan

SURFACE LEVEL: 582 AHD
EASTING:
NORTHING:

PIT No: 7
PROJECT No: 88224.00
DATE: 17/8/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
582	0.2	TOPSOIL - dry to moist, red/brown, fine to medium grained silty sand with rootlets										
		SANDY CLAY - stiff, moist, red/brown, medium plasticity sandy clay		B	0.3		pp = 200					
					0.4							
					0.6							
581	0.9	SILTY SAND - loose, dry to moist, yellow/brown, fine grained silty sand		D	1.0			1				
		- from 1.4m dense, red/brown silty sand with trace of quartz gravels (cemented)		D	1.5							
580	2			D	2.0			2				
	2.4	SILTY CLAY - stiff to very stiff, red/brown, medium plasticity silty clay with some sands and cobbles		D	2.5		pp = 200-250					
579	3			D	3.0			3				
				D	3.5							
578	4.0	Pit discontinued at 4.0m - limit of investigation		D	4.0			4				

RIG: Kubota KX057-4 mini excavator

LOGGED: APH

SURVEY DATUM: MGA94

WATER OBSERVATIONS: No free groundwater observed

REMARKS:

- ☐ Sand Penetrometer AS1289.6.3.3
☐ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND					
A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)

TEST PIT LOG

CLIENT: CIC Australia Ltd
PROJECT: Proposed Subdivision - Deferred Areas
LOCATION: Stage 3 Jumping Creek, Queanbeyan

SURFACE LEVEL: 585.5 AHD
EASTING:
NORTHING:

PIT No: 8
PROJECT No: 88224.00
DATE: 17/8/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
585	0.1	TOPSOIL - moist, brown, fine to coarse grained silty sand with rootlets		D	0.1							
	0.4	DACITE - high strength, slightly weathered, blue/grey, highly fractured dacite		D	0.4							
584		Pit discontinued at 0.4m - bucket refusal										
1												
583												
2												
3												
582												
4												
581												

RIG: Kubota KX057-4 mini excavator

LOGGED: APH

SURVEY DATUM: MGA94

WATER OBSERVATIONS: No free groundwater observed

REMARKS:

- ☐ Sand Penetrometer AS1289.6.3.3
☐ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND					
A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	▷	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

TEST PIT LOG

CLIENT: CIC Australia Ltd
PROJECT: Proposed Subdivision - Deferred Areas
LOCATION: Stage 3 Jumping Creek, Queanbeyan

SURFACE LEVEL: 591 AHD
EASTING:
NORTHING:

PIT No: 9
PROJECT No: 88224.00
DATE: 17/8/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
591		TOPSOIL - moist, brown, fine to coarse grained silty gravelly sand with rootlets		D	0.1							
	0.2	SANDY GRAVEL - dense, moist, brown, fine to coarse grained sandy gravel										
	0.4	SHALE - high strength, slightly weathered, blue/grey, highly fractured shale		B	0.4							
					0.6							
590	1			D	1.0							
	1.3	Pit discontinued at 1.3m - bucket refusal		D	1.3							
589	2											
588	3											
587	4											

RIG: Kubota KX057-4 mini excavator

LOGGED: APH

SURVEY DATUM: MGA94

WATER OBSERVATIONS: No free groundwater observed

REMARKS:

- ☐ Sand Penetrometer AS1289.6.3.3
☐ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND					
A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	▷	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

TEST PIT LOG

CLIENT: CIC Australia Ltd
PROJECT: Proposed Subdivision - Deferred Areas
LOCATION: Stage 3 Jumping Creek, Queanbeyan

SURFACE LEVEL: 593 AHD
EASTING:
NORTHING:

PIT No: 10
PROJECT No: 88224.00
DATE: 17/8/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
593	0.1	TOPSOIL - moist, brown, fine to coarse grained silty sand with rootlets		D	0.1							
	0.3	DACITE - high strength, slightly weathered, blue/grey dacite		D	0.3							
		Pit discontinued at 0.3m - bucket refusal										
592	1											
591	2											
590	3											
589	4											

RIG: Kubota KX057-4 mini excavator

LOGGED: APH

SURVEY DATUM: MGA94

WATER OBSERVATIONS: No free groundwater observed

REMARKS:

- ☐ Sand Penetrometer AS1289.6.3.3
☐ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND					
A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	▷	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

TEST PIT LOG

CLIENT: CIC Australia Ltd
PROJECT: Proposed Subdivision - Deferred Areas
LOCATION: Stage 3 Jumping Creek, Queanbeyan

SURFACE LEVEL: 602 AHD
EASTING:
NORTHING:

PIT No: 11
PROJECT No: 88224.00
DATE: 17/8/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
602	0.05	TOPSOIL - dry to moist, brown, fine to medium grained silty sand with rootlets and some gravels		D	0.1							
	0.3	SANDY GRAVEL - medium dense, moist, orange/brown, fine to coarse grained sandy gravel										
		DACITE - medium to high strength, moderately to highly weathered, yellow/brown dacite		D	0.5							
	0.7	- from 0.7 high strength, moderately weathered Pit discontinued at 0.7m - bucket refusal										
601	1											
600	2											
599	3											
598	4											

RIG: Kubota KX057-4 mini excavator

LOGGED: APH

SURVEY DATUM: MGA94

WATER OBSERVATIONS: No free groundwater observed

REMARKS:

- ☐ Sand Penetrometer AS1289.6.3.3
☐ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND					
A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	▷	Water seep	S	Standard penetration test
E	Environmental sample	≡	Water level	V	Shear vane (kPa)

TEST PIT LOG

CLIENT: CIC Australia Ltd
PROJECT: Proposed Subdivision - Deferred Areas
LOCATION: Stage 3 Jumping Creek, Queanbeyan

SURFACE LEVEL: 605 AHD
EASTING:
NORTHING:

PIT No: 12
PROJECT No: 88224.00
DATE: 17/8/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
605	0.2	TOPSOIL - dry to moist, brown, fine to medium grained silty sand with rootlets and some gravels		D	0.1							
		SILTSTONE - medium to high strength, moderately to slightly weathered, brown, highly fractured siltstone										
		- from 0.4m high strength, slightly weathered, brown/grey, highly fractured with some large cobble sizes (150 - 200mm)		D	0.5							
604	0.8	Pit discontinued at 0.8m - bucket refusal										
603	1											
	2											
602	3											
601	4											

RIG: Kubota KX057-4 mini excavator

LOGGED: APH

SURVEY DATUM: MGA94

WATER OBSERVATIONS: No free groundwater observed

REMARKS:

- ☐ Sand Penetrometer AS1289.6.3.3
☐ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND					
A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)

TEST PIT LOG

CLIENT: CIC Australia Ltd
PROJECT: Proposed Subdivision - Deferred Areas
LOCATION: Stage 3 Jumping Creek, Queanbeyan

SURFACE LEVEL: 595.5 AHD
EASTING:
NORTHING:

PIT No: 13
PROJECT No: 88224.00
DATE: 17/8/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
595	0.2	TOPSOIL - dry to moist, brown, fine to medium grained silty sand with rootlets and some gravels		D	0.1							
		SANDY GRAVEL - medium dense, dry to moist, yellow/brown, fine to coarse grained sandy gravel with cobbles										
	0.6			D	0.5							
	0.7	SANDY GRAVEL - dense, dry to moist, yellow/brown grey, fine to coarse grained sandy gravel grading to rock		D	0.7							
594	0.8	SILTSTONE - high strength, slightly weathered, brown/grey siltstone										
1		Pit discontinued at 0.8m - bucket refusal							1			
2									2			
3									3			
4									4			

RIG: Kubota KX057-4 mini excavator

LOGGED: APH

SURVEY DATUM: MGA94

WATER OBSERVATIONS: No free groundwater observed

REMARKS:

- ☐ Sand Penetrometer AS1289.6.3.3
☐ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND					
A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)

TEST PIT LOG

CLIENT: CIC Australia Ltd
PROJECT: Proposed Subdivision - Deferred Areas
LOCATION: Stage 3 Jumping Creek, Queanbeyan

SURFACE LEVEL: 589 AHD
EASTING:
NORTHING:

PIT No: 14
PROJECT No: 88224.00
DATE: 17/8/2015
SHEET 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
589	0.2	TOPSOIL - dry to moist, brown, fine to medium grained silty sand with rootlets and some gravels		D	0.1							
		SILTY CLAYEY GRAVEL - medium dense, moist, red/brown, fine to coarse grained, medium plasticity silty clayey gravel		D	0.5							
588	0.7	SHALE - high strength, slightly weathered, blue, highly fractured shale										
588	1.1			D	1.0				1			
	1.1	Pit discontinued at 1.1m - bucket refusal										
587	2								2			
586	3								3			
585	4								4			

RIG: Kubota KX057-4 mini excavator

LOGGED: APH

SURVEY DATUM: MGA94

WATER OBSERVATIONS: No free groundwater observed

REMARKS:

- ☐ Sand Penetrometer AS1289.6.3.3
- ☐ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test (s(50) (MPa)
		PL(D)	Point load diametral test (s(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)



Appendix D

Results of Laboratory Testing (1 page)

Determination of Emerson Class Number of Soil

Client:	DOUGLAS PARTNERS PTY LTD		Project No:	88224.00	
Project:	Proposed Subdivision		Report No:	GL15-052	
			Report Date:	24/08/2015	
Location:	Jumping Creek		Date of Test:	21/08/2015	
			Page:	1 of 1	

Sample No.	Depth (m)	Description	Water Type	Water Temp	Class No.
Pit 1	0.1	Silty Sand	Distilled	17°C	8
Pit 3	0.1	Silty Sand	Distilled	17°C	4
Pit 4	1.0	Silty Sand	Distilled	17°C	4
Pit 7	0.4	Sandy Clay	Distilled	17°C	4
Pit 9	0.4	Sandy Gravel	Distilled	17°C	4
Pit 12	0.1	Silty Sand w/ Some Gravel	Distilled	17°C	8
Pit 13	0.1	Silty Sand w/ Some Gravel	Distilled	17°C	8
Pit 14	0.5	Silty Clay Gravel	Distilled	17°C	4

Test Methods: AS 1289 3.8.1

Sampling Methods: Sampled by Canberra Engineering Department

Remarks: -

Appendix E

AGS Guidelines Extract

PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007
APPENDIX C: LANDSLIDE RISK ASSESSMENT
QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY

QUALITATIVE MEASURES OF LIKELIHOOD

Approximate Annual Probability		Implied Indicative Landslide Recurrence Interval		Description	Descriptor	Level
Indicative Value	Notional Boundary					
10 ⁻¹	5x10 ⁻²	10 years	20 years	The event is expected to occur over the design life.	ALMOST CERTAIN	A
10 ⁻²		100 years		The event will probably occur under adverse conditions over the design life.	LIKELY	B
10 ⁻³	5x10 ⁻³	1000 years	200 years	The event could occur under adverse conditions over the design life.	POSSIBLE	C
10 ⁻⁴	5x10 ⁻⁴	10,000 years	2000 years	The event might occur under very adverse circumstances over the design life.	UNLIKELY	D
10 ⁻⁵	5x10 ⁻⁵	100,000 years	20,000 years	The event is conceivable but only under exceptional circumstances over the design life.	RARE	E
10 ⁻⁶	5x10 ⁻⁶	1,000,000 years	200,000 years	The event is inconceivable or fanciful over the design life.	BARELY CREDIBLE	F

Note: (1) The table should be used from left to right; use Approximate Annual Probability or Description to assign Descriptor, not *vice versa*.

QUALITATIVE MEASURES OF CONSEQUENCES TO PROPERTY

Approximate Cost of Damage		Description	Descriptor	Level
Indicative Value	Notional Boundary			
200%	100%	Structure(s) completely destroyed and/or large scale damage requiring major engineering works for stabilisation. Could cause at least one adjacent property major consequence damage.	CATASTROPHIC	1
60%		Extensive damage to most of structure, and/or extending beyond site boundaries requiring significant stabilisation works. Could cause at least one adjacent property medium consequence damage.	MAJOR	2
20%	40%	Moderate damage to some of structure, and/or significant part of site requiring large stabilisation works. Could cause at least one adjacent property minor consequence damage.	MEDIUM	3
5%	10%	Limited damage to part of structure, and/or part of site requiring some reinstatement stabilisation works.	MINOR	4
0.5%	1%	Little damage. (Note for high probability event (Almost Certain), this category may be subdivided at a notional boundary of 0.1%. See Risk Matrix.)	INSIGNIFICANT	5

- Notes:** (2) The Approximate Cost of Damage is expressed as a percentage of market value, being the cost of the improved value of the unaffected property which includes the land plus the unaffected structures.
- (3) The Approximate Cost is to be an estimate of the direct cost of the damage, such as the cost of reinstatement of the damaged portion of the property (land plus structures), stabilisation works required to render the site to tolerable risk level for the landslide which has occurred and professional design fees, and consequential costs such as legal fees, temporary accommodation. It does not include additional stabilisation works to address other landslides which may affect the property.
- (4) The table should be used from left to right; use Approximate Cost of Damage or Description to assign Descriptor, not *vice versa*

PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

APPENDIX C: – QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY (CONTINUED)

QUALITATIVE RISK ANALYSIS MATRIX – LEVEL OF RISK TO PROPERTY

LIKELIHOOD		CONSEQUENCES TO PROPERTY (With Indicative Approximate Cost of Damage)				
	Indicative Value of Approximate Annual Probability	1: CATASTROPHIC 200%	2: MAJOR 60%	3: MEDIUM 20%	4: MINOR 5%	5: INSIGNIFICANT 0.5%
A – ALMOST CERTAIN	10 ⁻¹	VH	VH	VH	H	M or L (5)
B – LIKELY	10 ⁻²	VH	VH	H	M	L
C – POSSIBLE	10 ⁻³	VH	H	M	M	VL
D – UNLIKELY	10 ⁻⁴	H	M	L	L	VL
E – RARE	10 ⁻⁵	M	L	L	VL	VL
F – BARELY CREDIBLE	10 ⁻⁶	L	VL	VL	VL	VL

Notes: (5) For Cell A5, may be subdivided such that a consequence of less than 0.1% is Low Risk.

(6) When considering a risk assessment it must be clearly stated whether it is for existing conditions or with risk control measures which may not be implemented at the current time.

RISK LEVEL IMPLICATIONS

Risk Level		Example Implications (7)
VH	VERY HIGH RISK	Unacceptable without treatment. Extensive detailed investigation and research, planning and implementation of treatment options essential to reduce risk to Low; may be too expensive and not practical. Work likely to cost more than value of the property.
H	HIGH RISK	Unacceptable without treatment. Detailed investigation, planning and implementation of treatment options required to reduce risk to Low. Work would cost a substantial sum in relation to the value of the property.
M	MODERATE RISK	May be tolerated in certain circumstances (subject to regulator's approval) but requires investigation, planning and implementation of treatment options to reduce the risk to Low. Treatment options to reduce to Low risk should be implemented as soon as practicable.
L	LOW RISK	Usually acceptable to regulators. Where treatment has been required to reduce the risk to this level, ongoing maintenance is required.
VL	VERY LOW RISK	Acceptable. Manage by normal slope maintenance procedures.

Note: (7) The implications for a particular situation are to be determined by all parties to the risk assessment and may depend on the nature of the property at risk; these are only given as a general guide.

PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

APPENDIX G - SOME GUIDELINES FOR HILLSIDE CONSTRUCTION

GOOD ENGINEERING PRACTICE

POOR ENGINEERING PRACTICE

ADVICE

GEOTECHNICAL ASSESSMENT	Obtain advice from a qualified, experienced geotechnical practitioner at early stage of planning and before site works.	Prepare detailed plan and start site works before geotechnical advice.
-------------------------	---	--

PLANNING

SITE PLANNING	Having obtained geotechnical advice, plan the development with the risk arising from the identified hazards and consequences in mind.	Plan development without regard for the Risk.
---------------	---	---

DESIGN AND CONSTRUCTION

HOUSE DESIGN	Use flexible structures which incorporate properly designed brickwork, timber or steel frames, timber or panel cladding. Consider use of split levels. Use decks for recreational areas where appropriate.	Floor plans which require extensive cutting and filling. Movement intolerant structures.
SITE CLEARING	Retain natural vegetation wherever practicable.	Indiscriminately clear the site.
ACCESS & DRIVEWAYS	Satisfy requirements below for cuts, fills, retaining walls and drainage. Council specifications for grades may need to be modified. Driveways and parking areas may need to be fully supported on piers.	Excavate and fill for site access before geotechnical advice.
EARTHWORKS	Retain natural contours wherever possible.	Indiscriminatory bulk earthworks.
CUTS	Minimise depth. Support with engineered retaining walls or batter to appropriate slope. Provide drainage measures and erosion control.	Large scale cuts and benching. Unsupported cuts. Ignore drainage requirements
FILLS	Minimise height. Strip vegetation and topsoil and key into natural slopes prior to filling. Use clean fill materials and compact to engineering standards. Batter to appropriate slope or support with engineered retaining wall. Provide surface drainage and appropriate subsurface drainage.	Loose or poorly compacted fill, which if it fails, may flow a considerable distance including onto property below. Block natural drainage lines. Fill over existing vegetation and topsoil. Include stumps, trees, vegetation, topsoil, boulders, building rubble etc in fill.
ROCK OUTCROPS & BOULDERS	Remove or stabilise boulders which may have unacceptable risk. Support rock faces where necessary.	Disturb or undercut detached blocks or boulders.
RETAINING WALLS	Engineer design to resist applied soil and water forces. Found on rock where practicable. Provide subsurface drainage within wall backfill and surface drainage on slope above. Construct wall as soon as possible after cut/fill operation.	Construct a structurally inadequate wall such as sandstone flagging, brick or unreinforced blockwork. Lack of subsurface drains and weepholes.
FOOTINGS	Found within rock where practicable. Use rows of piers or strip footings oriented up and down slope. Design for lateral creep pressures if necessary. Backfill footing excavations to exclude ingress of surface water.	Found on topsoil, loose fill, detached boulders or undercut cliffs.
SWIMMING POOLS	Engineer designed. Support on piers to rock where practicable. Provide with under-drainage and gravity drain outlet where practicable. Design for high soil pressures which may develop on uphill side whilst there may be little or no lateral support on downhill side.	
DRAINAGE		
SURFACE	Provide at tops of cut and fill slopes. Discharge to street drainage or natural water courses. Provide general falls to prevent blockage by siltation and incorporate silt traps. Line to minimise infiltration and make flexible where possible. Special structures to dissipate energy at changes of slope and/or direction.	Discharge at top of fills and cuts. Allow water to pond on bench areas.
SUBSURFACE	Provide filter around subsurface drain. Provide drain behind retaining walls. Use flexible pipelines with access for maintenance. Prevent inflow of surface water.	Discharge roof runoff into absorption trenches.
SEPTIC & SULLAGE	Usually requires pump-out or mains sewer systems; absorption trenches may be possible in some areas if risk is acceptable. Storage tanks should be water-tight and adequately founded.	Discharge sullage directly onto and into slopes. Use absorption trenches without consideration of landslide risk.
EROSION CONTROL & LANDSCAPING	Control erosion as this may lead to instability. Revegetate cleared area.	Failure to observe earthworks and drainage recommendations when landscaping.


DRAWINGS AND SITE VISITS DURING CONSTRUCTION

DRAWINGS	Building Application drawings should be viewed by geotechnical consultant	
SITE VISITS	Site Visits by consultant may be appropriate during construction/	


INSPECTION AND MAINTENANCE BY OWNER

OWNER'S RESPONSIBILITY	Clean drainage systems; repair broken joints in drains and leaks in supply pipes. Where structural distress is evident see advice. If seepage observed, determine causes or seek advice on consequences.	
------------------------	--	--

EXAMPLES OF **GOOD** HILLSIDE PRACTICE



EXAMPLES OF **POOR** HILLSIDE PRACTICE



Appendix F

CSIRO Publication

Foundation Maintenance and Footing Performance: A Homeowner's Guide



BTF 18
replaces
Information
Sheet 10/91

Buildings can and often do move. This movement can be up, down, lateral or rotational. The fundamental cause of movement in buildings can usually be related to one or more problems in the foundation soil. It is important for the homeowner to identify the soil type in order to ascertain the measures that should be put in place in order to ensure that problems in the foundation soil can be prevented, thus protecting against building movement.

This Building Technology File is designed to identify causes of soil-related building movement, and to suggest methods of prevention of resultant cracking in buildings.

Soil Types

The types of soils usually present under the topsoil in land zoned for residential buildings can be split into two approximate groups – granular and clay. Quite often, foundation soil is a mixture of both types. The general problems associated with soils having granular content are usually caused by erosion. Clay soils are subject to saturation and swell/shrink problems.

Classifications for a given area can generally be obtained by application to the local authority, but these are sometimes unreliable and if there is doubt, a geotechnical report should be commissioned. As most buildings suffering movement problems are founded on clay soils, there is an emphasis on classification of soils according to the amount of swell and shrinkage they experience with variations of water content. The table below is Table 2.1 from AS 2870, the Residential Slab and Footing Code.

Causes of Movement

Settlement due to construction

There are two types of settlement that occur as a result of construction:

- Immediate settlement occurs when a building is first placed on its foundation soil, as a result of compaction of the soil under the weight of the structure. The cohesive quality of clay soil mitigates against this, but granular (particularly sandy) soil is susceptible.
- Consolidation settlement is a feature of clay soil and may take place because of the expulsion of moisture from the soil or because of the soil's lack of resistance to local compressive or shear stresses. This will usually take place during the first few months after construction, but has been known to take many years in exceptional cases.

These problems are the province of the builder and should be taken into consideration as part of the preparation of the site for construction. Building Technology File 19 (BTF 19) deals with these problems.

Erosion

All soils are prone to erosion, but sandy soil is particularly susceptible to being washed away. Even clay with a sand component of say 10% or more can suffer from erosion.

Saturation

This is particularly a problem in clay soils. Saturation creates a bog-like suspension of the soil that causes it to lose virtually all of its bearing capacity. To a lesser degree, sand is affected by saturation because saturated sand may undergo a reduction in volume – particularly imported sand fill for bedding and blinding layers. However, this usually occurs as immediate settlement and should normally be the province of the builder.

Seasonal swelling and shrinkage of soil

All clays react to the presence of water by slowly absorbing it, making the soil increase in volume (see table below). The degree of increase varies considerably between different clays, as does the degree of decrease during the subsequent drying out caused by fair weather periods. Because of the low absorption and expulsion rate, this phenomenon will not usually be noticeable unless there are prolonged rainy or dry periods, usually of weeks or months, depending on the land and soil characteristics.

The swelling of soil creates an upward force on the footings of the building, and shrinkage creates subsidence that takes away the support needed by the footing to retain equilibrium.

Shear failure

This phenomenon occurs when the foundation soil does not have sufficient strength to support the weight of the footing. There are two major post-construction causes:

- Significant load increase.
- Reduction of lateral support of the soil under the footing due to erosion or excavation.
- In clay soil, shear failure can be caused by saturation of the soil adjacent to or under the footing.

GENERAL DEFINITIONS OF SITE CLASSES

Class	Foundation
A	Most sand and rock sites with little or no ground movement from moisture changes
S	Slightly reactive clay sites with only slight ground movement from moisture changes
M	Moderately reactive clay or silt sites, which can experience moderate ground movement from moisture changes
H	Highly reactive clay sites, which can experience high ground movement from moisture changes
E	Extremely reactive sites, which can experience extreme ground movement from moisture changes
A to P	Filled sites
P	Sites which include soft soils, such as soft clay or silt or loose sands; landslip; mine subsidence; collapsing soils; soils subject to erosion; reactive sites subject to abnormal moisture conditions or sites which cannot be classified otherwise

Tree root growth

Trees and shrubs that are allowed to grow in the vicinity of footings can cause foundation soil movement in two ways:

- Roots that grow under footings may increase in cross-sectional size, exerting upward pressure on footings.
- Roots in the vicinity of footings will absorb much of the moisture in the foundation soil, causing shrinkage or subsidence.

Unevenness of Movement

The types of ground movement described above usually occur unevenly throughout the building's foundation soil. Settlement due to construction tends to be uneven because of:

- Differing compaction of foundation soil prior to construction.
- Differing moisture content of foundation soil prior to construction.

Movement due to non-construction causes is usually more uneven still. Erosion can undermine a footing that traverses the flow or can create the conditions for shear failure by eroding soil adjacent to a footing that runs in the same direction as the flow.

Saturation of clay foundation soil may occur where subfloor walls create a dam that makes water pond. It can also occur wherever there is a source of water near footings in clay soil. This leads to a severe reduction in the strength of the soil which may create local shear failure.

Seasonal swelling and shrinkage of clay soil affects the perimeter of the building first, then gradually spreads to the interior. The swelling process will usually begin at the uphill extreme of the building, or on the weather side where the land is flat. Swelling gradually reaches the interior soil as absorption continues. Shrinkage usually begins where the sun's heat is greatest.

Effects of Uneven Soil Movement on Structures

Erosion and saturation

Erosion removes the support from under footings, tending to create subsidence of the part of the structure under which it occurs. Brickwork walls will resist the stress created by this removal of support by bridging the gap or cantilevering until the bricks or the mortar bedding fail. Older masonry has little resistance. Evidence of failure varies according to circumstances and symptoms may include:

- Step cracking in the mortar beds in the body of the wall or above/below openings such as doors or windows.
- Vertical cracking in the bricks (usually but not necessarily in line with the vertical beds or perpendes).


Isolated piers affected by erosion or saturation of foundations will eventually lose contact with the bearers they support and may tilt or fall over. The floors that have lost this support will become bouncy, sometimes rattling ornaments etc.

Seasonal swelling/shrinkage in clay

Swelling foundation soil due to rainy periods first lifts the most exposed extremities of the footing system, then the remainder of the perimeter footings while gradually permeating inside the building footprint to lift internal footings. This swelling first tends to create a dish effect, because the external footings are pushed higher than the internal ones.

The first noticeable symptom may be that the floor appears slightly dished. This is often accompanied by some doors binding on the floor or the door head, together with some cracking of cornice mitres. In buildings with timber flooring supported by bearers and joists, the floor can be bouncy. Externally there may be visible dishing of the hip or ridge lines.

As the moisture absorption process completes its journey to the innermost areas of the building, the internal footings will rise. If the spread of moisture is roughly even, it may be that the symptoms will temporarily disappear, but it is more likely that swelling will be uneven, creating a difference rather than a disappearance in symptoms. In buildings with timber flooring supported by bearers and joists, the isolated piers will rise more easily than the strip footings or piers under walls, creating noticeable doming of flooring.



As the weather pattern changes and the soil begins to dry out, the external footings will be first affected, beginning with the locations where the sun's effect is strongest. This has the effect of lowering the external footings. The doming is accentuated and cracking reduces or disappears where it occurred because of dishing, but other cracks open up. The roof lines may become convex.

Doming and dishing are also affected by weather in other ways. In areas where warm, wet summers and cooler dry winters prevail, water migration tends to be toward the interior and doming will be accentuated, whereas where summers are dry and winters are cold and wet, migration tends to be toward the exterior and the underlying propensity is toward dishing.

Movement caused by tree roots

In general, growing roots will exert an upward pressure on footings, whereas soil subject to drying because of tree or shrub roots will tend to remove support from under footings by inducing shrinkage.

Complications caused by the structure itself

Most forces that the soil causes to be exerted on structures are vertical – i.e. either up or down. However, because these forces are seldom spread evenly around the footings, and because the building resists uneven movement because of its rigidity, forces are exerted from one part of the building to another. The net result of all these forces is usually rotational. This resultant force often complicates the diagnosis because the visible symptoms do not simply reflect the original cause. A common symptom is binding of doors on the vertical member of the frame.

Effects on full masonry structures

Brickwork will resist cracking where it can. It will attempt to span areas that lose support because of subsided foundations or raised points. It is therefore usual to see cracking at weak points, such as openings for windows or doors.

In the event of construction settlement, cracking will usually remain unchanged after the process of settlement has ceased.

With local shear or erosion, cracking will usually continue to develop until the original cause has been remedied, or until the subsidence has completely neutralised the affected portion of footing and the structure has stabilised on other footings that remain effective.

In the case of swell/shrink effects, the brickwork will in some cases return to its original position after completion of a cycle, however it is more likely that the rotational effect will not be exactly reversed, and it is also usual that brickwork will settle in its new position and will resist the forces trying to return it to its original position. This means that in a case where swelling takes place after construction and cracking occurs, the cracking is likely to at least partly remain after the shrink segment of the cycle is complete. Thus, each time the cycle is repeated, the likelihood is that the cracking will become wider until the sections of brickwork become virtually independent.

With repeated cycles, once the cracking is established, if there is no other complication, it is normal for the incidence of cracking to stabilise, as the building has the articulation it needs to cope with the problem. This is by no means always the case, however, and monitoring of cracks in walls and floors should always be treated seriously.

Upheaval caused by growth of tree roots under footings is not a simple vertical shear stress. There is a tendency for the root to also exert lateral forces that attempt to separate sections of brickwork after initial cracking has occurred.

The normal structural arrangement is that the inner leaf of brickwork in the external walls and at least some of the internal walls (depending on the roof type) comprise the load-bearing structure on which any upper floors, ceilings and the roof are supported. In these cases, it is internally visible cracking that should be the main focus of attention, however there are a few examples of dwellings whose external leaf of masonry plays some supporting role, so this should be checked if there is any doubt. In any case, externally visible cracking is important as a guide to stresses on the structure generally, and it should also be remembered that the external walls must be capable of supporting themselves.

Effects on framed structures

Timber or steel framed buildings are less likely to exhibit cracking due to swell/shrink than masonry buildings because of their flexibility. Also, the doming/dishing effects tend to be lower because of the lighter weight of walls. The main risks to framed buildings are encountered because of the isolated pier footings used under walls. Where erosion or saturation cause a footing to fall away, this can double the span which a wall must bridge. This additional stress can create cracking in wall linings, particularly where there is a weak point in the structure caused by a door or window opening. It is, however, unlikely that framed structures will be so stressed as to suffer serious damage without first exhibiting some or all of the above symptoms for a considerable period. The same warning period should apply in the case of upheaval. It should be noted, however, that where framed buildings are supported by strip footings there is only one leaf of brickwork and therefore the externally visible walls are the supporting structure for the building. In this case, the subfloor masonry walls can be expected to behave as full brickwork walls.

Effects on brick veneer structures

Because the load-bearing structure of a brick veneer building is the frame that makes up the interior leaf of the external walls plus perhaps the internal walls, depending on the type of roof, the building can be expected to behave as a framed structure, except that the external masonry will behave in a similar way to the external leaf of a full masonry structure.

Water Service and Drainage

Where a water service pipe, a sewer or stormwater drainage pipe is in the vicinity of a building, a water leak can cause erosion, swelling or saturation of susceptible soil. Even a minuscule leak can be enough to saturate a clay foundation. A leaking tap near a building can have the same effect. In addition, trenches containing pipes can become watercourses even though backfilled, particularly where broken rubble is used as fill. Water that runs along these trenches can be responsible for serious erosion, interstrata seepage into subfloor areas and saturation.

Pipe leakage and trench water flows also encourage tree and shrub roots to the source of water, complicating and exacerbating the problem.

Poor roof plumbing can result in large volumes of rainwater being concentrated in a small area of soil:

- Incorrect falls in roof guttering may result in overflows, as may gutters blocked with leaves etc.

- Corroded guttering or downpipes can spill water to ground.
- Downpipes not positively connected to a proper stormwater collection system will direct a concentration of water to soil that is directly adjacent to footings, sometimes causing large-scale problems such as erosion, saturation and migration of water under the building.

Seriousness of Cracking

In general, most cracking found in masonry walls is a cosmetic nuisance only and can be kept in repair or even ignored. The table below is a reproduction of Table C1 of AS 2870.

AS 2870 also publishes figures relating to cracking in concrete floors, however because wall cracking will usually reach the critical point significantly earlier than cracking in slabs, this table is not reproduced here.

Prevention/Cure

Plumbing

Where building movement is caused by water service, roof plumbing, sewer or stormwater failure, the remedy is to repair the problem. It is prudent, however, to consider also rerouting pipes away from the building where possible, and relocating taps to positions where any leakage will not direct water to the building vicinity. Even where gully traps are present, there is sometimes sufficient spill to create erosion or saturation, particularly in modern installations using smaller diameter PVC fixtures. Indeed, some gully traps are not situated directly under the taps that are installed to charge them, with the result that water from the tap may enter the backfilled trench that houses the sewer piping. If the trench has been poorly backfilled, the water will either pond or flow along the bottom of the trench. As these trenches usually run alongside the footings and can be at a similar depth, it is not hard to see how any water that is thus directed into a trench can easily affect the foundation's ability to support footings or even gain entry to the subfloor area.

Ground drainage

In all soils there is the capacity for water to travel on the surface and below it. Surface water flows can be established by inspection during and after heavy or prolonged rain. If necessary, a grated drain system connected to the stormwater collection system is usually an easy solution.

It is, however, sometimes necessary when attempting to prevent water migration that testing be carried out to establish watertable height and subsoil water flows. This subject is referred to in BTF 19 and may properly be regarded as an area for an expert consultant.

Protection of the building perimeter


It is essential to remember that the soil that affects footings extends well beyond the actual building line. Watering of garden plants, shrubs and trees causes some of the most serious water problems.

For this reason, particularly where problems exist or are likely to occur, it is recommended that an apron of paving be installed around as much of the building perimeter as necessary. This paving

CLASSIFICATION OF DAMAGE WITH REFERENCE TO WALLS

Description of typical damage and required repair	Approximate crack width limit (see Note 3)	Damage category
Hairline cracks	<0.1 mm	0
Fine cracks which do not need repair	<1 mm	1
Cracks noticeable but easily filled. Doors and windows stick slightly	<5 mm	2
Cracks can be repaired and possibly a small amount of wall will need to be replaced. Doors and windows stick. Service pipes can fracture. Weathertightness often impaired	5–15 mm (or a number of cracks 3 mm or more in one group)	3
Extensive repair work involving breaking-out and replacing sections of walls, especially over doors and windows. Window and door frames distort. Walls lean or bulge noticeably, some loss of bearing in beams. Service pipes disrupted	15–25 mm but also depend on number of cracks	4

Gardens for a reactive site



should extend outwards a minimum of 900 mm (more in highly reactive soil) and should have a minimum fall away from the building of 1:60. The finished paving should be no less than 100 mm below brick vent bases.

It is prudent to relocate drainage pipes away from this paving, if possible, to avoid complications from future leakage. If this is not practical, earthenware pipes should be replaced by PVC and backfilling should be of the same soil type as the surrounding soil and compacted to the same density.

Except in areas where freezing of water is an issue, it is wise to remove taps in the building area and relocate them well away from the building – preferably not uphill from it (see BTF 19).

It may be desirable to install a grated drain at the outside edge of the paving on the uphill side of the building. If subsoil drainage is needed this can be installed under the surface drain.

Condensation

In buildings with a subfloor void such as where bearers and joists support flooring, insufficient ventilation creates ideal conditions for condensation, particularly where there is little clearance between the floor and the ground. Condensation adds to the moisture already present in the subfloor and significantly slows the process of drying out. Installation of an adequate subfloor ventilation system, either natural or mechanical, is desirable.

Warning: Although this Building Technology File deals with cracking in buildings, it should be said that subfloor moisture can result in the development of other problems, notably:

- Water that is transmitted into masonry, metal or timber building elements causes damage and/or decay to those elements.
- High subfloor humidity and moisture content create an ideal environment for various pests, including termites and spiders.
- Where high moisture levels are transmitted to the flooring and walls, an increase in the dust mite count can ensue within the living areas. Dust mites, as well as dampness in general, can be a health hazard to inhabitants, particularly those who are abnormally susceptible to respiratory ailments.

The garden

The ideal vegetation layout is to have lawn or plants that require only light watering immediately adjacent to the drainage or paving edge, then more demanding plants, shrubs and trees spread out in that order.

Overwatering due to misuse of automatic watering systems is a common cause of saturation and water migration under footings. If it is necessary to use these systems, it is important to remove garden beds to a completely safe distance from buildings.

Existing trees

Where a tree is causing a problem of soil drying or there is the existence or threat of upheaval of footings, if the offending roots are subsidiary and their removal will not significantly damage the tree, they should be severed and a concrete or metal barrier placed vertically in the soil to prevent future root growth in the direction of the building. If it is not possible to remove the relevant roots without damage to the tree, an application to remove the tree should be made to the local authority. A prudent plan is to transplant likely offenders before they become a problem.

Information on trees, plants and shrubs

State departments overseeing agriculture can give information regarding root patterns, volume of water needed and safe distance from buildings of most species. Botanic gardens are also sources of information. For information on plant roots and drains, see Building Technology File 17.

Excavation

Excavation around footings must be properly engineered. Soil supporting footings can only be safely excavated at an angle that allows the soil under the footing to remain stable. This angle is called the angle of repose (or friction) and varies significantly between soil types and conditions. Removal of soil within the angle of repose will cause subsidence.

Remediation

Where erosion has occurred that has washed away soil adjacent to footings, soil of the same classification should be introduced and compacted to the same density. Where footings have been undermined, augmentation or other specialist work may be required. Remediation of footings and foundations is generally the realm of a specialist consultant.

Where isolated footings rise and fall because of swell/shrink effect, the homeowner may be tempted to alleviate floor bounce by filling the gap that has appeared between the bearer and the pier with blocking. The danger here is that when the next swell segment of the cycle occurs, the extra blocking will push the floor up into an accentuated dome and may also cause local shear failure in the soil. If it is necessary to use blocking, it should be by a pair of fine wedges and monitoring should be carried out fortnightly.

This BTF was prepared by John Lewer FAIB, MIAMA, Partner, Construction Diagnosis.

The information in this and other issues in the series was derived from various sources and was believed to be correct when published.

The information is advisory. It is provided in good faith and not claimed to be an exhaustive treatment of the relevant subject.

Further professional advice needs to be obtained before taking any action based on the information provided.

Distributed by

CSIRO PUBLISHING PO Box 1139, Collingwood 3066, Australia

Freecall 1800 645 051 Tel (03) 9662 7666 Fax (03) 9662 7555 www.publish.csiro.au

Email: publishing.sales@csiro.au

© CSIRO 2003. Unauthorised copying of this Building Technology file is prohibited